

# IN SHOP COOLER PREP


## DO NOT PLUG IN UNIT



- Cooler should be upright for a minimum of 6 hours




- Remove lid- Check float assembly and connectors




- Push in buttons and lubricate Faucet Housing with Food Grade Silicone



- Install Filter system



- Check Drain Plug



- Attached water line to inlet valve on back of cooler
- Turn on water.....Check for leaks....All water connections to and from filters as well as all water connections inside cooler.
- Let cooler fill up completely.....Open both faucets to confirm tanks are both filled.....



- Plug in Cooler and push switches to on position.....Check temperatures to confirm Hot and cold units are both operating.....
- Let run over night.....

## *When ready for installation...*

- Turn off power.....
- Disconnect water Line
- Drain Tanks
- Attach Lid
- Move to location and install

*877-Kool-Tek (877-566-5835)*  
*www.KoolTekCoolers.com*